BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT31178

APPROVED SCHEDULE - B

.E/BTP/BBMP/E-PMT/03/2018-19, Date: 01.08.2018

Pro ding new pipeline and repairs to existing pipelines in ward no.07 byatarayanapura, kodigehalli Subdivision

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of VENKATESH V ( )	
				In Figures	In Words
1	26.1	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Asphalt surface road.	Cum	313.0	Rupees Three Hundred Thirteen Only
2	39.15	Cutting of road surface for pipeline trenches and disposing of the excavated stuff as directed including barricading, danger lighting etc., in the Cement Concrete road.	Cum	559.0	Rupees Five Hundred Fifty Nine Only
3	156.6	KSRB 2-2.2: Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually(other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff levelled and neatly dressed, disposed earth to be levelled and exceeding 50m and lift up to 1.5m, excavated surface levelled and neatly dressed as per specifications.	Cum	145.0	Rupees One Hundred Forty Five Only
4	1160	Providing and fixing Chorinated Poly Venyl Chloride(CPVC) pipes confirming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass treaded fittings including fixing the pipe with clamp at 1.oo m spacing.This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete (inertnal work exposed on wall).PRED SR 2016-17(P-231, Item No.15mm nominal OD PIPES) 63mm dia of 6Kg/Cm2	Sqm	106.0	Rupees One Hundred Six Only
5	104.4	KSRB 2.4: Refilling available earth around the pipe lines, cables in layers not exceeding 20 cms in depth , compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications	Cum	56.0	Rupees Fifty Six Only
6	221.85	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	91.0	Rupees Ninety One Only
7	78.3	KSRB 4-1.3:Providing and laying position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth including cost of all materials, labour, HOM of machienry, curing complete as per specifications.	Cum	4481.0	Rupees Four Thousand Four Hundred Eighty One Only
8	52.2	KSRB 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size grader granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 15 cms. thick well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinary, curing complete as per specifications.	Cum	5103.0	Rupees Five Thousand One Hundred Three Only
9	20	KSRB 13-6.2-2: Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	No	147.0	Rupees One Hundred Forty Seven Only
10	20	KSRB 13-6.3-7: Providing and fixing in position brass gate valve with C.I.wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	No	1889.0	Rupees One Thousand Eight Hundred Eighty Nine Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

31/10

31/10